

# CONTRACT PRICE FOR STADIUM AUTHORITY

## Gold 1 Garage (G1G)

General Conditions		Quantity	Unit	Unit Cost	Line Cost
	General Conditions		LS		
	Work Access		LS		
	Permitting		LS		
				<b>Sub-Total</b>	
Repairs		Quantity	Unit	Unit Cost	Line Cost
A.1	Vertical Concrete Repairs	25	SF		
A.2	Full Depth Tee Flange Repair	50	SF		
A.3	Partial Depth Overhead Tee Flange Repair	50	SF		
A.4	Partial Depth Topside Repair	25	SF		
A.5	Rout and Seal Crack Repair	100	LF		
A.6	Remove and Replace Existing Sealant Joint	100	LF		
A.7	Epoxy Injection Crack Repair	50	LF		
A.8	Replace Plastic Precast Connection Covers	30	EA		
A.9	Recoat traffic coating at top level of garage as noted on drawings.	1	LS		
				<b>Sub-Total</b>	
				<b>Total</b>	

# CONTRACT PRICE FOR STADIUM AUTHORITY

## West General Robinson Street Garage (WGRSG)

General Conditions		Quantity	Unit	Unit Cost	Line Cost
	General Conditions		LS		
	Work Access		LS		
	Permitting		LS		
				<b>Sub-Total</b>	
Repairs		Quantity	Unit	Unit Cost	Line Cost
B.1	Vertical Concrete Repairs	75	SF		
B.2	Full Depth Tee Flange Repair	50	SF		
B.3	Partial Depth Overhead Tee Flange Repair	50	SF		
B.4	Partial Depth Topside Repair	30	SF		
B.5	Partial Depth Beam Repair	30	SF		
B.6	Tee Flange Connection Repair	5	EA		
B.7	Drain Replacement	5	EA		
B.8	Rout and Seal Crack Repairs	100	LF		
B.9	Double Tee Stem Repair	25	SF		
B.10	Remove and Replace entire length of Urethane Sealant joints between curb and slab at Ramp on North side of the building	500	LF		
B.11	Remove and Replace Screen Anchor with ½" Threaded Rod installed w/ Hilti HIT-HY 270 or approved equivalent.	8	EA		
B.12	Remove and Replace all urethane sealant joints in concrete wash at location noted on Level 9.	150	LF		
B.13	Epoxy Inject Crack at underside of precast tee flange on Level 10	15	LF		
B.14	Remove and replace expansion joints at 3 locations on ninth and tenth level as noted on drawings. Include 25 LF of urethane sealant replacement on flashing over elevator expansion joint.	1	LS		
				<b>Sub-Total</b>	
				<b>Total</b>	

# CONTRACT PRICE FOR SPORTS & EXHIBITION AUTHORITY

## North Shore Garage (NSG)

General Conditions		Quantity	Unit	Unit Cost	Line Cost
	General Conditions		LS		
	Work Access		LS		
	Permitting		LS		
				<b>Sub-Total</b>	
Repairs		Quantity	Unit	Unit Cost	Line Cost
C.1	Vertical Concrete Repairs	25	SF		
C.2	Full Depth Tee Flange Repair	40	SF		
C.3	Partial Depth Overhead Tee Flange Repair	40	SF		
C.4	Partial Depth Topside Repair	30	SF		
C.5	Partial Depth Beam Repair	20	SF		
C.6	Tee Flange Connection Repair	15	EA		
C.7	Drain Replacement	40	EA		
C.8	Rout and Seal Crack Repair	75	LF		
				<b>Sub-Total</b>	
				<b>Total</b>	

## Tribute to the Children (TTC)

General Conditions		Quantity	Unit	Unit Cost	Line Cost
	General Conditions		LS		
	Work Access		LS		
	Permitting		LS		
				<b>Sub-Total</b>	
Repairs		Quantity	Unit	Unit Cost	Line Cost
D.1	Mortar Joint Repairs	600	LF		
D.2	Gravel Planter Infill	1	EA		
				<b>Sub-Total</b>	
				<b>Total</b>	

## CONTRACT PRICING FOR ALL WORK (SA & SEA)

### Project Total - Quantity Discount

General Conditions		Quantity	Unit	Unit Cost	Line Cost
	General Conditions		LS		
	Work Access		LS		
	Permitting		LS		
				<b>Sub-Total</b>	

Repairs		Quantity	Unit	Unit Cost	Line Cost
	Drain Replacement (B.7, C.7)	45	EA		
	Remove and Replace Existing Sealant Joint (A.6, B.10, B.12)	750	LF		
	Mortar Joint Repairs – Total (D.1)	600	LF		
	Gravel Planter Infill (D.2)	1	EA		
	Full Depth Tee Flange Repair (A.2, B.2, C.2)	140	SF		
	Partial Depth Beam Repair (B.5, C.5)	50	SF		
	Partial Depth Overhead Tee Flange Repair (A.3, B.3, C.3)	140	SF		
	Partial Depth Topside Repair (A.4, B.4, C.4)	85	SF		
	Rout and Seal Crack Repair (A.5, B.8, C.8)	275	LF		
	Tee Flange Connection Repair (B.6, C.6)	20	EA		
	Vertical Concrete Repairs (A.1, B.1, C.1)	125	SF		
	Epoxy Injection Crack Repair (A.7, B.13)	65	LF		
	Replace Plastic Precast Connection Covers (A.8)	30	EA		
	Recoat traffic coating at top level of garage as noted on drawings. (A.9)	1	LS		
	Double Tee Stem Repair (B.9)	25	SF		
	Remove and Replace Screen Anchor with ½" Threaded Rod installed w/ Hilti HIT-HY 270 or approved equivalent. (B.11)	8	EA		
	Remove and replace expansion joints at 3 locations on ninth and tenth level as noted on drawings. Include 25 LF of urethane sealant replacement on flashing over elevator expansion joint. (B.14)	1	LS		
				<b>Sub-Total</b>	

				<b>Total</b>	
--	--	--	--	--------------	--

**BASE BID – Concrete Repairs**

- A. For all labor, material, services and equipment necessary for completion of the work specified, the Bidder bids
- B. Complete Repair Bid Form and spreadsheet (“Bid Tab”) and provide total price for each section.

**TOTAL OVERALL GOLD 1 GARAGE BASE BID PRICE**

**Total base bid price for all work, complete, in accordance with the Bid Package**

\$ \_\_\_\_\_

(Written)

\$ \_\_\_\_\_

(Numerals)

**TOTAL OVERALL WEST GENERAL ROBINSON STREET GARAGE BASE BID PRICE**

**Total base bid price for all work, complete, in accordance with the Bid Package**

\$ \_\_\_\_\_

(Written)

\$ \_\_\_\_\_

(Numerals)

**TOTAL OVERALL NORTH SHORE GARAGE BASE BID PRICE**

**Total base bid price for all work, complete, in accordance with the Bid Package**

\$ \_\_\_\_\_

(Written)

\$ \_\_\_\_\_

(Numerals)

**TOTAL OVERALL TRIBUTE TO CHILDREN BASE BID PRICE**

**Total base bid price for all work, complete, in accordance with the Bid Package**

\$ \_\_\_\_\_

(Written)

\$ \_\_\_\_\_

(Numerals)

**QUANTITY DISCOUNT TOTAL BID PRICE**

Total of the bid price for all work, complete, and in accordance with the Bid Package. If the contractor is awarded the contract for both Sports & Exhibition Authority and the Stadium Authority, the total project cost can include possible quantity discounts.

\$ \_\_\_\_\_

(Written)

\$ \_\_\_\_\_

(Numerals)